

## **ATLAS TK MASONRY, LLC**

1241 Grace St.

Mansfield, Ohio 44905

(419) 989-2293

[atlasasonryohio@outlook.com](mailto:atlasasonryohio@outlook.com)



### **PROPOSAL #3**

Date: 6/16/2025

Project: MOESC

890 W. 4th St.

Mansfield, OH

We hereby propose to perform the labor and supply material and equipment necessary to complete the work described below.

1. Excavation and removal of spoils to install concrete footing
2. Furnish and install concrete footing w/#5 rebar mat at bottom of the footer
3. Furnish and install 1 course CMU foundation grouted solid
4. Furnish and install CMU backup at brick piers to be grouted solid
5. Furnish and install brick veneer piers w/wall ties, flashing, term bar, drip edge, sealant and cell vents at each face
6. Furnish and install 8" Splitface CMU walls back to back between brick piers grouted solid
7. Furnish and install cast stone caps at piers and base
8. Wash all units upon completion
9. Furnish and install top soil, grass seed and straw at backfilled footer around the sign base

Amount: \$ 16,600.00

All of the labor performed is to be completed in a substantial, workman like manner based on the schedule to be determined at a later date.

Respectfully Submitted,

Scott Kanz

Atlas TK Masonry, LLC.

**Proposal expires in 30 days**